

भारतसरकार
GOVERNMENT OF INDIA
भाभापरमाणुअनुसंधानकेंद्र
BHABHA ATOMIC RESEARCH CENTRE
Nuclear Recycle Board
R & WM, INRPO, Tarapur

Ref.: BARC (T)/NRB/SS lining AVS Annex./2023/OPA-29

Date: 04/01/2024

To

Sub: Collection of SS plates, fabrication including welding, edge preparation and installation of SS lining plates at various areas of AVS Annex., BARC Tarapur.

Dear Sir/Madam,

You are requested to submit your quotation for the job as per the specifications (annexure -A) attached through e-tendering mode on website <https://eprocure.gov.in/eprocure/app>.

General Instructions:

1. Details of work to be carried out is given in the annexure - A. Please quote accordingly. You may also visit our office with prior appointment to evaluate any specific details of work.
2. To participate in the tender, Bidders are required to login in the Home page of the website <https://eprocure.gov.in/eprocure/app>
3. Bidders have to fill the excel documents and upload the same without renaming it.
4. Work shall be initiated immediately and completed within **Three (03)** calendar months after the date of receipt of the Work order. Any deviation in this regard shall be clearly indicated in your quotation.
5. Last date of submission of e-bids is **11/01/2023** upto **12:00 hrs.**
6. E-Bids will be opened on **12/01/2023** at **14:00** hrs. on that website. You are requested to send your representative for witnessing the same.
7. 100% payment will be made within 30/90 days against Invoice and a certificate from competent authority indicating that the works carried out to our full satisfaction.

Thanking you

Yours truly

A.K.Rai
EIC, FMRH, WM

Annexure-I

Ref. No.:- BARC (T)/NRB/SS lining AVS Annex./2023/OPA-29 Date: 04/01/2024

A- Scope of work:

The following is the scope of work for Collection of SS plates, fabrication including weld edge preparation and installation of SS lining plates at floor 3 of AVS Annex., BARC Tarapur.

1. Collection of SS plates of from WM Plant.
 2. Cutting the SS plates as per the site condition.
 3. Edge preparation, root fit-up, root welding and final welding using GTAW method.
 4. There shall be no gap between the adjacent SS Plates.
 5. Carrying out the DPT on root fit up and after final weld.
 6. Cleaning of site in all respect.
-

Quotation

BARC (T)/NRB/SS lining AVS Annex./2023/OPA- 29

Date: 04/01/2024

Name of work: - Collection of SS plates, fabrication including weld edge preparation and installation of SS lining plates at floor 3 of AVS Annex., BARC Tarapur.

Sr. No.	Description of Work	Qty.	Unit	Unit Rate (Rs.)	Amount (Rs.)
1.	Fabrication & erection of SS lining. Preparation of fabrication drawings, supply of required material other than FIM, collection of FIM from department store, preparation of sheet cutting layout, fabrication of lining works, inspection, testing and welding by GTAW of lining works. Root and final DPT of weld joints.	2.5	M.T.		
	Rs (In words).....				

(Sign & Seal of the Contractor)

Schedule –B (FIM)

Ref. No.:- BARC (T)/NRB/SS lining AVS Annex./2023/OPA-29 Date:04/01/2024

Name of work: - Collection of SS plates, fabrication including weld edge preparation and installation of SS lining plates at floor 3 of AVS Annex., BARC Tarapur.

Sl. No.	Description	Quantity	Remarks
1.	SS Plates	2.5 MT	To be collected from WM Stores
2.	Electricity	As per requirement	Free; at one point near the place of work.
3.	Raw Water	As per requirement	Free; at one point near the place of work.
4.	Filler Wire	As per requirement	Free; at one point near the place of work.

Project Manager, INRPO

NRB BARC Tarapur